

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 30 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-9-117

RECEIVED OCT 27 2003 KCC WICHITA 15-083-10178-0000

Form CP-4 September 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: American Warrior, Inc. Address: P.O. Box 399 Phone: (620) 275-2963 Operator License #: 4058 Type of Well: Oil Docket #: (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR) The plugging proposal was approved on: 10-21-03 (Date) by: Mike Maier (KCC District Agent's Name) Is ACO-1 filed? [X] Yes [] No If not, is well log attached? [] Yes [] No Producing Formation(s): List All (if needed attach another sheet) Mississippian Depth to Top: 4379' Bottom: 4398' T.D. 4398'

API Number: 15 - Drilled 1961 Lease Name: Antrim Well Number: A-2 Spot Location (QQQQ): NW - NE - 660 Feet from [X] North / [] South Section Line 1980 Feet from [X] East / [] West Section Line Sec. 17 Twp. 21 S. R. 22 [] East [X] West County: Hodgeman Date Well Completed: 8-25-61 Plugging Commenced: 10-22-03 Plugging Completed: 10-22-03

Show depth and thickness of all water, oil and gas formations.

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Row 1: Mississippian, oil/water, 4379', 4398', 8 5/8, 263', None. Row 2: (blank), (blank), (blank), (blank), 5 1/2, 4388', None.

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed, from feet to feet each set.

Mixed & pumped 30 sacks cement with 200# of hulls and displaced to bottom plug off open hole, shut in with 550 psi let sit 30 minutes release pressure and perforate casing @ 606', pump 120 sacks cement with 100# of hulls, casing full, pump 40 sacks cement down 8 5/8 braden head and pressure to 500 psi, well plugged.

Name of Plugging Contractor: Swift Services, Inc. License #: 32382 Address: Ness City, KS 67560 Name of Party Responsible for Plugging Fees: American Warrior, Inc. State of Kansas County, Ness, ss.

Scott Corsair (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature] (Address) 210 Avenue A, Bazine, KS 67516

SUBSCRIBED and SWORN TO before me this 23rd day of October, 20 03. Bernice Moore Notary Public My Commission Expires: 2/7/06

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

