

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Hodgeman County, Sec. 22 Twp. 21S Rge. (E) 23 (W)

Location as "NE/CNW%SW%" or footage from lines C SE NW

Lease Owner Beardmore Drilling Co.

Lease Name TETEN Well No. 1

Office Address Beacon Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed February 11 1964

Application for plugging filed February 11 1964

Application for plugging approved February 11 1964


Plugging commenced February 11 1964

Plugging completed February 11 1964

Reason for abandonment of well or producing formation No oil or gas found
in commercial quantities.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Hugh Scott, Sublette, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4757 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	200'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugs set as follows: 700' with 25 sacks, 200' with 25 sacks, 40' with 15 sacks. Plug down 8:00 p.m.

RECEIVED
STATE CORPORATION COMMISSION

FEB 19 1964

CONSERVATION DIVISION
Wichita, Kansas

2-19-64

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.

Address 1425 Wichita Plaza Building, Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss.

Wilson Rains (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains

Wilson Rains
1425 Wichita Plaza, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of February, 1964

Shirley Keck
Shirley Keck Notary Public.

My commission expires January 8, 1968

ROTARY DRILLING LOG

Operator: Beardmore Drilling Co.
No. 1 TETEN
C SE NW Sec. 22-21S-23W
Hodgeman County, Kansas

Contractor: Rains & Williamson
Oil Co.

Commenced: 1-28-64
Completed: 2-11-64

Remarks: 8-5/8" casing set
at 207' with 175
sacks common cement.

Formations:

Surface Clay	40
Sand	80
Shale	730
Shale & Red Bed	965
Anhydrite	980
Shale	1060
Sand & Shale	1250
Shale & Red Bed	1515
Anhydrite	1550
Shale	1990
Shale & Shells	2345
Shale & Lime	2410
Lime & Shale	3605
Shale & Lime	3900
Lime & Shale	4120
Lime	4243
Lime & Shale	4390
Lime	4425
Lime & Shale	4605
Lime & Chert	4700
Lime	4757

Rotary Total Depth 4757

RECEIVED
STATE CORPORATION COMMISSION

FEB 19 1964

CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is
true and correct to the best
of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
Wilson Rains
Partner

Subscribed and sworn to before me, a Notary Public in and for the
State of Kansas, County of Sedgwick, this 13th day of February, 1964.

My Commission Expires:
January 8, 1968

Shirley Keck
Shirley Keck, Notary Public