


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Hodgeman County, Sec. 21 Twp. 21 Rge. 23 (E) (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines SE SE SE $\frac{1}{4}$
Lease Owner Kingwood Oil Company, etal
Lease Name Myrtle Folkerts Well No. 1
Office Address Cravens Building, Oklahoma City, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) dry
Date well completed December 19 51
Application for plugging filed Feb. 9 19 52
Application for plugging approved Feb. 9 19 52
Plugging commenced Feb. 11 19 52
Plugging completed Feb. 11 19 52
Reason for abandonment of well or producing formation dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well C. D. Stough
Producing formation Depth to top Bottom Total Depth of Well 4564 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	159'	none
				5 1/2	4531'	3293'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with crushed rock to 4275 ft., dumped 5 sacks with dump bailer, top of cement 4235 ft. Mudded hole to 160 ft., set rock bridge, dumped 15 sacks cement, top of cement 115 ft. Mudded hole to 35 ft. Set rock bridge at 35 ft., dumped 10 sacks for cap.

FFR 1352 2-29-52

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor The Miller Casing Pulling Company
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick
L. C. Sponenberg (employee of M. B. Armer, SS. employee of owner or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. B. Armer
By: L. C. Sponenberg (Address)

SUBSCRIBED AND SWORN to before me this 28th day of February, 1952

Notary Public

My commission expires Sept. 17, 1955 23-8890-s 6-51-20M

PLUGGING
FILE SEC 21 R 23C
PAGE 144 LINE 29

LOG

Company: Kingwood Oil Company et al.
 Contractor: Speer Drilling Company
 Drilling commenced: 6/27/51
 Drilling completed: 7/16/51
 Elevation: 2346 Cr. 2349 D. P. 2352 R. B.

Farm: Myrtle Folkerts - well #1
 Location: SE SE SE 21-21S-23W,
 Hodgeman County, Kansas
 Casing record: 8-5/8" at 159'
 cemented w/125 sacks
 5 1/2" set at 4531' cemented
 w/200 sacks.

(figures below indicate bottoms)

Sand, shale & shells	159
Shale & red bed	460
Sand	530
Shale	585
Shale & red bed	950
Anhydrite	963
Red bed	1045
Sand	1240
Shale & shells	1335
Shale, shells & red bed	1516
Red bed	1563
Anhydrite	1610
Shale & shells	2470
Shale & lime	3204
Shale	3364
Shale & lime	3620
Lime	3740
Lime & shale	3880
Lime	3937
Lime & shale	4031
Lime	4194
Shale & lime	4256
Lime	4296
Lime & shale	4322
Lime	4418
Lime & shale	4455
Lime	4502
Lime & shale	4535

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

SPEER DRILLING COMPANY

By *J. Speer*

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a notary public, in and for said County and State this 19th day of July, 1951.

Hazel Walton
 Notary Public

My commission expires Sept. 17, 1951.

PLUGGING
 FILE SEC 21T 21 R 23W
 PAGE 14 LINE 29