


STATE OF KANSAS
STATE CORPORATION COMMISSION.

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Barton County, Sec. 36 Twp. 16 Rge. 11W E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
C NE NE
Lease Owner Brougner Oil, Inc.
Lease Name Alden A#1 Well No. _____
Office Address Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 7/19/79 _____ 19____
Plugging completed 7/27/79 _____ 19____
Reason for abandonment of well or producing formation
depleted.

If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Rankin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3373
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	265	none
				5 1/2"	3371	2039'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded to 3150' and ran 5 sacks cement. Loaded hole, shot pipe at 2527', 2430', 2333', 2233', 2112', 2018', pulled 63 joints. Pumped 5 sacks hulls, 20 sacks gel, 100 sacks 50-50 pos.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

JUL 31 1979

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS COUNTY OF RICE, ss.
B. DARBELL KELES (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) B. Darbell Keles
CHASE, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 30th day of July, 1979

Margaret Melcher
Notary Public.

My commission expires



15-009-20372-0000

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

ALDEN "A" #1
C NE NE Section 26-16S-11W
Barton County, Kansas

Commenced: May 1, 1969
Completed: May 10, 1969

OPERATOR - Alpine Drilling Co., Inc.

DEPTH		FORMATION	REMARKS
From	To		
0	281	Rock, shale and shells	Ran 14 joints 8-5/8" casing, set @ 265' w/175 sacks cement.
281	695	Shale and shells	
695	724	Anhydrite	
724	1470	Shale and shells	
1470	1655	Shale	
1655	1827	Shale and lime w/sand streaks	
1827	1965	Lime and shale	
1965	2080	Shale	
2080	2836	Shale and lime	
2836	3100	Lime	
3100	3179	Lime and shale	
3179	3373	Lime	
3373	TD		Ran 101 joints 5-1/2" casing, set @ 3371' w/150 sacks cement.

I, E. E. HALL, certify this is a correct copy of the Drillers' Log for the well drilled in the C NE NE Section 26-16S-11W, Barton County, Kansas, to the best of my knowledge and belief.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SE
COUNTY OF SEDGWICK)

RECEIVED
STATE CORPORATION COMMISSION

JUN 13 1979

Before me, the undersigned, a Notary Public within and for said County and State, on this 14 day of May, 1969, personally appeared E. E. Hall to me personally known to be the identical person who executed the within and foregoing instrument, and he acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.

My Commission Expires Feb. 1, 1972.

Barbara J. Layton
Barbara J. Layton, Notary Public

