

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-20449-00-00
Spot: NESWNE Sec/Twnshp/Rge: 16-33S-11W
3583 feet from S Section Line, 1657 feet from E Section Line
Lense Name: PAGE C Well #: 13
County: BARBER Total Vertical Depth: 4570 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4450		WITH 2 SX CMT
PROD	5.5	4569	0	WITH 200 SX CMT
SURF	8.625	201		WITH 175 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/30/2017 9:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Revd. from: ALAN VRATIL Company: HERMAN L LOEB Phone: (620) 886-2419

Proposed Plugging Method: SET CIBP @ 4450' & 2 SX CMT. PLUG AT 1200' WITH 50 SX CMT. PERFORATE AT 600' & CIRCULATE CMT IN & OUT 5 1/2" & 5 1/2" ANNULUS TO SURFACE.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/30/2017 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4450' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER.
SPOT 50 SX CMT AT 1200' TO SHUT OFF ANY CASING LEAKS BELOW. TAG TOC @ 842'. PERFORATE 5 1/2" CASING AT 600'. PUMPED DOWN 5 1/2" CASING WITH 200 SX CMT FILLING 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4503	4510		
4480	4517		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

INVOICED
AUG 29 2017

District: 01

Signed Stephan J. Pfeifer
(TECHNICIAN)
SA

RECEIVED
JUL 17 2017
KCC DODGE CITY