

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-01447-00-00

Spot: NESENE SW

Sec/Twnshp/Rge: 34-25S-8E

1850 feet from S Section Line, 2390 feet from W Section Line

Lease Name: CREW

Well #: 9

County: GREENWOOD

Total Vertical Depth: 2605 feet

Operator License No.: 5697

Op Name: JACKSON BROTHERS, L.L.C.

Address: 116 E 3RD ST
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2604		65 SX
SURF	8.625	203		0 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/03/2017 9:30 AM

Plug Co. License No.: 6112

Plug Co. Name: LONG DRILLING COMPANY, LLC

Proposal Revd. from: ROSCOE G. JACKSON II

Company:

Phone: (620) 583-5122

Proposed Plugging Method: 1. 50 ft. cement plug inside 4.500" casing at 2520-2470 ft. 2. 50 ft. cement plug inside and outside 4.500" at 1250-1200 ft. 3. Continuous cement plug inside and outside 4.500" from 250 ft. to land surface.

Plugging Proposal Received By: MICHAEL HEFFERN

Witness Type: PARTIAL

Date/Time Plugging Completed: 08/04/2017 12:00 AM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

spotted 7 sxs cement w/dump baler @ 2520', ran tubing to 1250', pumped 20 sxs cement, pulled tubing to 250', pumped 80 sxs cement to surface, casing shot @ 1250' & 250', gel spacers between cement plugs

Perfs:

Top	Bot	Thru	Comments
2556	2567		

RECEIVED
KCC DIST #3
AUG 14 2017
CHANUTE, KS

MH

INVOICED
AUG 29 2017

Remarks:

Plugged through: TBG

District: 03

Signed

Mich Heffern
(TECHNICIAN)

8545 A+2510 Dump Baker
4 AUGUST 2017 PAID BY JBLIC CHECK #8993 = \$3,371.92

810 E 7th
PO Box 92
EUREKA, KS 67045
(620) 583-5561



Cement or Acid Field Report
Ticket No. **3440**
Foreman STEVENHEAD
Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
8-4-17	1008	CRAW 9	34	25S	8E	Greenwood	Ks.
Customer Jackson Bros LLC			Unit #		Driver		
Mailing Address 116 E 3 rd			103		Rick		
City Eureka			112		Alan M		
State Ks			115		Allen B		
Zip Code 67045							

Job Type PZA Hole Depth _____ Slurry Vol. _____ Tubing 2 3/4 1250'
Casing Depth _____ Hole Size _____ Slurry Wt. _____ Drill Pipe _____
Casing Size & Wt. 4 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other _____
Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: SAFETY Meeting! Rig up to 2 3/4 Tubing. Break circulation w/ Fresh
Water. Pump 200' Gal spacer, Mix 30 sks Cement. Spot at 1250'. Pull out
Tubing. Rig up to 4 1/2 casing. Mix 80 sks Cement. 250' to surface inside
& outside of 4 1/2 casing.

Job complete Rig down

Total 110 sks 60/40 Pozmix Cement 4 1/2 Gal

Thank you

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	750.00	750.00
C107	15	Mileage	3.95	59.25
C203	110	60/40 Pozmix Cement	12.75	1402.50
C206	375*	Gal 4%	.20	75.00
C206	200*	Gal spacer	.20	40.00
E108A	4.23700	Tow mileage Bulk Truck	N/C	345.00
E108A		Tow mileage Bulk Truck Crawl # 8	0116	345.00
C113	3100	8000l Uae Truck	85.00	255.00
C224	3000 gal	CITY WATER	10.00/1000	30.00
		-5% DISCOUNT		-177.47
		Subtotal		3301.75
		Sales Tax		247.64

Authorization Roscoe Jackson II Title CO-MANAGER

Total
\$ 3371.92

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.