

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-167-23781-00-00  
Spot: NWNESWNW Sec/Twnshp/Rge: 13-15S-12W  
1629 feet from N Section Line, 847 feet from W Section Line  
Lease Name: WEBER Well #: 1  
County: RUSSELL Total Vertical Depth: 3325 feet

Operator License No.: 33813  
Op Name: JASON OIL COMPANY, LLC  
Address: 3718- 183RD ST PO BOX 701  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3356	1990	200 SX
SURF	8.625	517		225 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/19/2017 8:00 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: SHELDON WEIGEL Company: JASON OIL COMPANY, LLC DBA Phone: (785) 483-4204

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/19/2017 2:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Sanded off perforations and topped with 5 sx cement. Cut casing at 1990'. Pulled casing to 1450' and pumped 125 sx cement w/200 # hulls. Pulled casing to 800' and pumped 50 sx cement w/100 # hulls. Pulled casing to 400' and pumped 40 sx cement w/100 # hulls. Pulled casing to 200'. Circulated cement to surface with 65 sx cement. Pulled casing and hole stayed full.

GPS: 38.75074 -098.61161

INVOKED  
AUG 24 2017

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

KCC WICHITA

JUL 20 2017

RECEIVED

JUN 26 2017