

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-203-20213-00-00  
Spot: SWNENENE Sec/Township/Rge: 24-19S-36W  
650 feet from N Section Line, 470 feet from E Section Line  
Lease Name: JF GROUP B Well #: 1-24  
County: WICHITA Total Vertical Depth: 5250 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>5214</u>	DVT		2403		WITH 415 SX CMT
Op Name: <u>LARIO OIL &amp; GAS COMPANY</u>	PROD	5.5	5139	0	WITH 260 SX CMT
Address: <u>301 S MARKET ST</u> <u>WICHITA, KS 67202</u>	SURF	8.625	348		WITH 265 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/29/2017 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Recvd. from: MIKE Company: LARIO OIL & GAS Phone: (620) 277-2149

Proposed Plugging Method: PUMP 150# HULLS WITH 300 SX CMT ON BOTTOM. RUN TBG TO 2430' & LOAD HOLE. CIRCULATE CMT TO SURFACE WITH 250 SX CMT. CHECK ANNULUS.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE  
Date/Time Plugging Completed: 06/29/2017 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 150 # HULLS AT 4474'. (NO CMT DUE TO OPERATOR ERROR). PUMP 310 SX CMT FROM 2413' TO 0'. TOP OFF WITH 10 SX CMT. PUMP 15 SX CMT DOWN THE ANNULUS.

Perfs:


Top	Bot	Thru	Comments
4507	4511		
4488	4511		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED  
JUL 10 2017  
KCC DODGE CITY



514

INVOICED  
AUG 29 2017