

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-203-20254-00-00
Spot: E2SWNWNW Sec/Twushp/Rge: 3-19S-35W
4359 feet from S Section Line, 4815 feet from E Section Line
Lease Name: CHRISTY FARMS Well #: 1-3
County: WICHITA Total Vertical Depth: 5230 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 S MARKET ST
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4550		WITH 2 SX CMT
DVT	5.5	2433		WITH 535 SX CMT
PROD	5.5	5059	0	WITH 270 SX CMT
SURF	8.625	369		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/12/2017 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: MIKE Company: LARIO OIL & GAS Phone: (620) 277-2149

Proposed Plugging Method: CIBP @ 4550' WITH 2 SX CMT. RUN TBG TO APPROX. 2500'. CIRCULATE CMT UP TO 500'. PULL TBG TO 500' & CIRCULATE CMT TO SURFACE. FILL ANNULUS WITH CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/12/2017 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 4550' WITH 2 SX CMT. RUN TBG TO 2508' & CIRCULATE CMT TO SURFACE WITH 240 SX CMT. TOP OFF WITH 10 SX CMT. COULD NOT PUMP INTO THE ANNULUS.

Perfs:


Top	Bot	Thru	Comments
4611	4619		

Remarks: USED 60/40 POZMIX 4% GEL BY QES.

Plugged through: TBG

District: 01

Signed


(TECHNICIAN)

RECEIVED
JUL 21 2017
KCC DODGE CITY