

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-21510-00-00
Spot: SESEWNNE Sec/Twnslp/Rge: 12-34S-34W
4066 feet from S Section Line, 1470 feet from E Section Line
Lease Name: SHORB Well #: 3-12
County: SEWARD Total Vertical Depth: 2918 feet

Operator License No.: 35006
Op Name: LIME ROCK RESOURCES II-A, LP
Address: 1111 BAGBY ST, SUITE 4600
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2570		WITH 2 SX CMT
PROD	4.5	2918	0	WITH 635 SX CMT
SURF	8.625	650		WITH 290 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/05/2017 12:00 PM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Revd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: SET CIBP @ 2570' WITH 2 SX CMT. PLUG AT 1620' WITH 30 SX CMT. PLUG AT 690' WITH CMT TO 0'. CHECK BACKSIDE WITH CMT TO 500#.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/06/2017 10:00 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

7/5/17: SET CIBP @ 2570' WITH 2 SX CMT. RAN CBL & FOUND TOC @ 170'. LOADED CASING & TEST. WOULD NOT TEST. 1ST PLUG AT 1620' WITH 50 SX CMT & 200# HULLS. 7/6/17: TAGGED CMT AT 940'. TESTED CASING TO 500# & HOLDING. 2ND PLUG AT 690' WITH 55 SX CMT TO 0'. PUMPED 35 SX CMT DOWN BACKSIDE. PRESSURED TO 200#. HOLDING.

Perfs:

Top	Bot	Thru	Comments
2680	2710		
2645	2657		
2614	2632		

INVOICED
7-21-17

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: TBG

District: 01

Signed: Kenny Sullivan
(TECHNICIAN)

RECEIVED
JUL 11 2017
KCC DODGE CITY