

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-093-20442-00-00
Spot: NWNWSESE Sec/Twnshp/Rge: 9-23S-36W
1250 feet from S Section Line, 1250 feet from E Section Line
Lease Name: DOEBBELING Well #: 2-9
County: KEARNY Total Vertical Depth: 3070 feet

Operator License No.: 33999
Op Name: LINN OPERATING, LLC
Address: 600 TRAVIS STE 1400
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2753		
PROD	5.5	3069	0	WITH 490 SX CMT
SURF	8.625	685		WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/27/2017 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PLUGGING PROPOSAL AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/28/2017 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

CIBP @ 2753'. 6/27/17: RUN TBG TO 2730' & SPOT 75 SX CMT WITH 150 # HULLS TO COVER CASING LEAK. 6/28/17: TAG TOC IN THE CASING AT 2100'. LOAD CASING & TEST TO 700#. HOLDING. RUN CBL. FOUND TOP OF GOOD CMT AT 1500'. SCATTERED CMT STRINGERS UP TO 650'. PERFORATE 4 HOLES AT 630'. RUN TBG TO 800'. CIRCULATE CMT TO SURFACE UP THE 5 1/2" CASING & THROUGH THE PERFS AT 630' UP THE 5 1/2" X 8 5/8" ANNULUS USING 190 SX CMT. STAYED FULL.

Top	Bot	Thru	Comments
2809	2900		


INVOICED

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY QUALITY. AUG 29 2017

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
JUL - 7 2017
KCC DODGE CITY

