

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-189-20086-00-00
Spot: SESENWSE Sec/Twnshp/Rge: 15-32S-39W
1397 feet from S Section Line, 1395 feet from E Section Line
Lease Name: YOUNGREN Well #: 2-15
County: STEVENS Total Vertical Depth: 2880 feet

Operator License No.: 33999
Op Name: LINN OPERATING, LLC
Address: 600 TRAVIS STE 1400
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2879	0	WITH 300 SX CMT
RBP		2717		
SURF	8.625	558		500 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/17/2017 9:30 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Revd. from: WES LOGAN Company: LINN OPERATING Phone: (620) 356-6961

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLJK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/17/2017 2:00 PM KCC Agent: KEN JEHLJK

Actual Plugging Report:

SPOT 100 SX CMT WITH 2% CC & 200# HULLS FROM 2462' TO 1400' THROUGH TBG. TOOH WITH TBG. FOUND TOC IN THE 5 1/2" CASING AT 1458'. LOAD & PRESSURE TEST CASING TO 500#. HOLDING. PERFORATE 4 HOLES AT 597'. INJECTION RATE 1 1/2 BPM AT 50 PSI. CIRCULATE CMT TO SURFACE THROUGH THE PERFS AT 597' USING 150 SX CMT LEAVING THE 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2723	2844		
2710	2712		
2589	2591		
2537	2539		
2470	2472		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: TBG

INVOICED
AUG 29 2017

District: 01

Signed *Ken Jehlik*
(TECHNICIAN)

RECEIVED
JUL 26 2017
KCC DODGE CITY *AD*