

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-26177-00-00
Spot: N2NESENE Sec/Twnshp/Rge: 13-19S-13W
1345 feet from N Section Line, 330 feet from E Section Line
Lease Name: BUTTON Well #: 1
County: BARTON Total Vertical Depth: 3555 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	757		350 sx

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/06/2017 12:00 AM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: JAY Company: SOUTHWIND DRILLING, INC. Phone: (620) 617-4477

Proposed Plugging Method: Ordered 215 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 07/06/2017 12:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st plug @3490 w/50 sx
2nd plug @800 w/50 sx
3rd plug @350 w/75 sx
4th plug @40 w/10 sx

Rathole 30 sx

Perfs:

Remarks: QUALITY

Plugged through: DP

INVOICED
AUG 29 2017

District: 04

Signed _____



(TECHNICIAN)

KCC WICHITA

JUL 20 2017

RECEIVED

JUL 12 2017