

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-009-25391-00-00
Spot: SWNWSNW Sec/Twnshp/Rge: 24-18S-15W
1920 feet from N Section Line, 1380 feet from W Section Line
Lease Name: FYLER Well #: 1
County: BARTON Total Vertical Depth: 3534 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3566	2268	160 SX
SURF	8.625	939		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/22/2017 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS, INC. DBA Phone: (785) 483-2169

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/22/2017 12:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded back to 3200' and pumped with 5 sx cement. Cut casing at 2268'. Pulled casing to 1450' and pumped 125 sx cement w/300 # hulls. Pulled casing to 950' and pumped 50 sx cement w/100 # hulls. Pulled casing to 600' and pumped 50 sx cement w/100 # hulls. Pulled casing to 200' and pumped 45 sx cement. Circulated cement to surface. Pulled casing and hole stayed full.

GPS: 38.69599 -098.56588

Perfs:

Top	Bot	Thru	Comments
3419	3423		
3404	3410		
3387	3391		
3104	3110		

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

District: 04

Signed

Bruce Rodie
(TECHNICIAN)

CM

KCC WICHITA

JUL 20 2017

RECEIVED

JUN 26 2017

INVOICED
AUG 29 2017