

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-25492-00-00  
Spot: E2NWNENW Sec/Twnshp/Rge: 5-16S-11W  
330 feet from N Section Line, 1750 feet from W Section Line  
Lease Name: DAVIDSON "A" Well #: 1  
County: BARTON Total Vertical Depth: 3360 feet

Operator License No.: 5259  
Op Name: MAI OIL OPERATIONS, INC.  
Address: 8411 PRESTON RD STE 800  
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3357	1845	175 SX
SURF	8.625	373		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/20/2017 12:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: ALLEN BANGERT Company: MAI OIL OPERATIONS, INC. DBA Phone: (785) 483-2169

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 06/20/2017 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded back to 2800' and topped with 5 sx cement. Cut casing at 1845'. Pulled casing to 1450' and pumped 125 sx cement w/300 # hulls. Pulled casing to 700' and pumped 50 sx cement w/100 # hulls. Pulled casing to 400' and pumped 50 sx cement w/100 # hulls. Pulled casing to 200' and pumped 50 sx cement. Circulated cement to surface. Pulled casing and hole stayed full.

GPS: 38.69599 -098.56588

Perfs:

Top	Bot	Thru	Comments
3314	3316		
3303	3308		

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

INVOICED  
AUG 29 2017

District: 04

Signed Bruce Rodie  
KCC WICHITA (TECHNICIAN) CM

JUN 26 2017

JUL 20 2017  
RECEIVED