

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-095-21808-00-00  
Spot: N2NESE Sec/Twnshp/Rge: 15-30S-7W  
2310 feet from S Section Line, 660 feet from E Section Line  
Lease Name: DUNKELBERGER Well #: B#4  
County: KINGMAN Total Vertical Depth: 4202 feet

Operator License No.: 4706  
Op Name: MESSENGER PETROLEUM, INC.  
Address: 525 S MAIN ST  
KINGMAN, KS 67068

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4198		125 SX
SURF	8.625	273		175 SX

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/20/2017 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: DAVE BRADY Company: QUALITY WELL SERVICE Phone: (620) 532-5400

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/20/2017 2:00 PM KCC Agent: STEVE VANGIESON

**Actual Plugging Report:**

SET CIBP AT 4020' & CAPPED WITH 2 SXS CEMENT. RECOVERED CASING FROM 5600' & PULLED TO 1300', WHERE 2 SKS OF GEL WAS CIRCULATED DOWN CASING. PULL CASING TO 1200' & SPOTTED 35 SX COMMON CEMENT. TAGGED CEMENT AT 750'. PULL CASING TO 900' & SPOTTED 35 SX CEMENT. PULLED CASING TO 325' & CIRCULATED CEMENT TO SURFACE WITH 150 SX CEMENT.

**Perfs:**

Top	Bot	Thru	Comments
4070	4130		


INVOICED  
11/3 29 7/17

Remarks: QUALITY WELL SERVICE COMMON CEMENT

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)



PRESSURE PUMPING LLC  
 PO Box 884, Chanute, KS 66720  
 620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT  
 CEMENT

TICKET NUMBER 54697

LOCATION Eldorado

FOREMAN Brad Butler

API # 15-023-23835 0061

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
8-10-17	5436	Samples B #3 Trj.	35	25	10E	Greenwood
CUSTOMER			TRUCK #			
M <sup>c</sup> Kelland Oil/ M <sup>s</sup> S Energy			DRIVER			
MAILING ADDRESS			TRUCK #			
403 Village Rd.			DRIVER			
CITY			TRUCK #			
Eldorado			DRIVER			
STATE			TRUCK #			
Ks.			DRIVER			
ZIP CODE			TRUCK #			
67042			DRIVER			

JOB TYPE	HOLE SIZE	HOLE DEPTH	CASING SIZE & WEIGHT
PTA			5 1/2"
CASING DEPTH	DRILL PIPE	TUBING	OTHER
SLURRY WEIGHT	SLURRY VOL	WATER gal/sk	CEMENT LEFT in CASING
DISPLACEMENT	DISPLACEMENT, PSI	MIX PSI	RATE

REMARKS: Holes shot in casing @ 900' and 250'  
 Safety Meeting: Rig up to tubing set @ 1800', pumped 15 Bbls Gel Ahead, Spot 25 SKs 60/40 Pozman cement with 42 Gel @ 1800'. Pull Tubing up to 900', pumped 2 Bbls water Ahead then Spot 20 SKs 60/40 Pozman cement with 42 Gel @ 900'. Pull Tubing up to 250', break circulation with water, mixed cement till we had good cement returns. Pull Tubing out of well, filled casing back up with cement. Rig up to 5 1/2" casing and squeezed cement into hole. Mixed with 8.5 Bbls = 52 SKs on Top Plug @ 250' to Surface.  
 Job complete - Test down

Thank you

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0450	1	PUMP CHARGE	1,500.00	1,500.00
CE0002	1.5	MILEAGE	7.15	107.25
CE0711	m/c	Bulk Truck charge	660.00	660.00
CC5829	97 SKS.	60/40 Pozman cement w/ 42 Gel	16.00	1,552.00
CC5965	300 lbs.	Gel - Spacers between Plugs	.30	90.00
WE0853	10 Hrs.	Water Truck	100.00	1,000.00
				4,909.25
		45% Discount		-2,209.16
		7.5% SALES TAX		67.73
		ESTIMATED TOTAL		2,767.82

Ravin 3737

AUTHORIZATION [Signature] TITLE \_\_\_\_\_ DATE \_\_\_\_\_

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.