

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-06791-00-00
Spot: SESWNENW Sec/Twnshp/Rge: 32-14S-13W
4125 feet from S Section Line, 3465 feet from E Section Line
Lease Name: OPDYCKE B Well #: 12
County: RUSSELL Total Vertical Depth: 2935 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	740		
PROD	6	2852		200 SX
SURF	10.75	281		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/30/2017 8:30 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: MARK ROBBEN Company: MURFIN DRILLING CO., INC. Phone: (785) 735-5371

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/ 700 # (70 sx) hulls.
Ordered an additional 200 sx 60/40 pozmix 4% gel cement.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 05/30/2017 4:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 275' Hole at 445'-475' casing parted around 740'. Ran tubing to 2875' (23' into open hole) and pumped 75 sx cement w/210 # hulls. Pulled tubing to 2190' and pumped 100 sx cement w/70 # hulls. Pulled tubing to 1280' and pumped 100 sx cement w/70 # hulls. Pulled tubing to 369' and pumped 40 sx cement. Circulated cement to the pit out of the backside (2 3/8" x 4 1/2"). POOH. Hooked to 4 1/2" casing and pumped 85 sx cement with well fluids circulated to pit. (4 1/2" x 6"). 6" x 10 3/4" had a slight vacuum. Ordered 200 sx cement. WOC. Hooked to 4 1/2" casing and pumped 140 sx cement. Circulated cement out of the 4 1/2" x 6" and shut in. Pumped 35 sx cement. Circulated cement out of the 6" x 10 3/4" and shut in with approximately 350 psi. Shut in 4 1/2" casing. Total amount of cement used was 575 sx w/350 # hulls.

GPS: 38.79590 -098.79221

Perfs:

Top	Bot	Thru	Comments
2852	2935		

Remarks: HURRICANE SERVICE INC. TICKET # 100744

Plugged through: TBG

District: 04

Signed

Ray Dinkel

KCC WICHITA

(TECHNICIAN)

CM

JUL 20 2017

RECEIVED

JUN 26 2017

INVOICED
AUG 29 2017