

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-175-22030-00-00
 Spot: NENESWSW Sec/Twnshp/Rge: 34-32S-32W
1250 feet from S Section Line, 1250 feet from W Section Line
 Lease Name: WALKER Well #: 2-34
 County: SEWARD Total Vertical Depth: 2772 feet

Operator License No.: 8061
 Op Name: OIL PRODUCERS, INC. OF KANSAS
 Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2575		WITH 2 SX CMT
CIBP		2730		
PROD	4.5	2772	0	WITH 450 SX CMT
SURF	8.625	1626		WITH 550 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/30/2017 8:30 AM
 Plug Co. License No.: 34141 Plug Co. Name: MOHEGAN WELL SERVICE, LLC
 Proposal Revd. from: DAVID HAYES Company: OIL PRODUCERS Phone: (620) 546-4456

Proposed Plugging Method: SET CIBP @ 2575' WITH 2 SX CMT. PLUG AT 1660' WITH 30 SX CMT. PLUG AT 450' WITH CMT TO 0'. CHECK BACKSIDE TO 500 PSI.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
 Date/Time Plugging Completed: 06/30/2017 11:30 AM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 2575' WITH 2 SX CMT. 1ST PLUG AT 1667' WITH 30 SX CMT. 2ND PLUG AT 463' WITH 70 SX CMT 0'. CHECK BACKSIDE WITH 1 SX CMT. PRESSURED TO 500#.

Perfs:

Top	Bot	Thru	Comments
2738	2742		
2679	2696		
2652	2659		
2616	2621		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY BASIC.

INVOICED
 AUG 29 2017

Plugged through: TBG

District: 01

Signed Kenny Sullivan
 (TECHNICIAN)

SA

RECEIVED
 JUL 11 2017
 KCC DODGE CITY