

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-40572-00-00

Spot: SESWNE

Sec/Twnshp/Rge: 33-33S-12E

3016 feet from S Section Line,

1719 feet from E Section Line

Lease Name: BEASON

Well #: 3

County: CHAUTAUQUA

Total Vertical Depth: 1700 feet

Operator License No.: 4448

Op Name: PERKINS OIL ENTERPRISES, INC.

Address: PO BOX 707
HOWARD, KS 67349

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	0		0 SX
SURF	6.625	0		0 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/21/2017 12:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: KEVIN WARDLOW

Company:

Phone: (620) 330-3666

Proposed Plugging Method: PERF WELL AT 275' RUN 1" PIPE TO TD PUMP GEL & 50' CEMENT PLUG PULL PIPE UP TO 650' PUMP A 50' PLUG PULL UP TO 275' PUMP CEMENT TO SURFACE IN CASING & BACKSIDE OF CASING PULL REST OF PIPE & TOP OFF

Plugging Proposal Received By: DUANE SIMS

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 06/21/2017 12:00 PM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 930' gelled hole and spotted 5 sack plug. Pulled up to 600' and spotted 5 sack plug. Pulled 1" and perforated casing at 275'. Ran 1" back into 275' and circulated cement to surface. Pulled 1" and topped well off. A total of 53 sacks of cement were used to plug this well. Well was cut off and location restored.

RECEIVED
KCC DIST # 3
JUL 24 2017
CHANUTE, KS

DS


INVOICED
AUG 29 2017

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR WITH KCC.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

STATEMENT

12939

ELMORE'S INC.

Box 87 - 776 HWY 99
Sedan, KS 67361
Cell: (620) 249-2519
Eve: (620) 725-5538

Date 6-21-17

Customer Perkins Oil Enterprise JUN 21 2017
Address _____
City _____ State _____ Zip _____

Qty.	Description	Price	Amount
7	hr Pulling Unit	120. ⁰⁰	480. ⁰⁰
3	hr Cement Pump	120. ⁰⁰	360. ⁰⁰
3	hr Water Truck	85. ⁰⁰	255. ⁰⁰
1	Bank Tank	85. ⁰⁰	85. ⁰⁰
53	Sks Cement	12.50	662. ⁵⁰
1	Sk Coe	16. ⁰⁰	16. ⁰⁰
1	Perforation Air 275'	200. ⁰⁰	200. ⁰⁰
930'	1" Tubing	10	93. ⁰⁰
			2151. ⁵⁰
	<u>Reason #3</u>	Tax	182. ⁸⁸
	Plug 500' Port 1" To 930'		2334. ³⁸
	Coe Make Spotted 5 Sks Cement		
	Pulled Up to 600' Spotted 5 Sks Cement		
	Pulled 1" Out Perforated Pos. Air 275'		
	Port 1" To 275' Cemented To		
	Surface with 93 Sks Pulled 1" Out		
	Spurred Down 1/2" Sucked Out Air		

Thank You - We appreciate your business!

Rec'd. by _____

TERMS: Account due upon receipt of services. A 1 1/2% Service Charge, which is an annual percentage rate of 18% will be charged to accounts after 30 days.

Handwritten initials and a checkmark.