

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-40571-00-00
Spot: NESWNE Sec/Twnshp/Rge: 33-33S-12E
3374 feet from S Section Line, 1738 feet from E Section Line
Lease Name: BEASON Well #: 4
County: CHAUTAUQUA Total Vertical Depth: 1698 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comment
<u>4448</u>	PROD	4.5	0		0 SX
Op Name: <u>PERKINS OIL ENTERPRISES, INC.</u>	SURF	6.625	0		0 SX
Address: <u>PO BOX 707</u> <u>HOWARD, KS 67349</u>					

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/22/2017 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: PERKINS OIL ENTERPRISE Company: _____ Phone: (620) 374-2133

Proposed Plugging Method: PERF 275' FROM TOP RUN 1" TO TD PUMP GEL & 50' CEMENT PLUG PULL UP TO 600' PUMP 50 PLUG PULL UP TO 275' PUMP PLUG TO SURFACE IN CASING & ON BACK SIDE OF CASING. PULL REST ON PIPE & TOP OFF.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 06/22/2017 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 960' gelled hole and spotted 5 sack plug. Pulled up to 600' and spotted 5 sack plug. Pulled up to 275' and circulated cement to surface inside and outside casing. Pulled 1" and topped well off. A total of 83 sacks of cement were used to plug this well. well was cut off and locaiton restored.

RECEIVED
KCC DIST #3
JUL 24 2017
CHANUTE, KS

DS


INVOICED
AUG 29 2017

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR WITH KCC.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

STATEMENT

12940

ELMORE'S INC.
 Box 87 - 776 HWY 99
 Sedan, KS 67361
 Cell: (620) 249-2519
 Eve: (620) 725-5538

Date 6-22-17

Customer Parkins Oil Enterprise 1011
 Address _____
 City _____ State _____ Zip _____

Qty.	Description	Price	Amount
4	hr Pulling Hoist	120.00	480.00
3	hr Compact Pump	120.00	360.00
3	hr Water Truck	85.00	255.00
1	Bank Tank	85.00	85.00
23	SKS Cement	12.50	287.50
1	Sk. Coe	16.00	16.00
1	Perforation Bit 2.25	200.00	200.00
960	1" Tubing	.10	96.00
			2529.50
	Plug Job Reason #4	Tax	215.01
	Ran 1" To 960' Coe Hole	B	2744.51
	Spotted 5 SKS Cement Pilled		
	Wrote 600' Spotted 5 SKS Cement		
	Wrote 1" Bit Perforated At 2.25		
	Ran 1" LN To 2.25 Cemented To		
	Surface Circulated W/ Back Side of		
	4 1/2" Sucked Out Bit		

Thank You - We appreciate your business!

Rec'd. by _____ *Sho*

TERMS: Account due upon receipt of services. A 1 1/2% Service Charge, which is an annual percentage rate of 18% will be charged to accounts after 30 days.

STOCKS 3/20/17 4301108 10-0115

INVOICED
 AUG 29 2017

