

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-01197-00-00
Spot: SWSENESE Sec/Twnshp/Rgc: 3-32S-15W
1500 feet from S Section Line, 500 feet from E Section Line
Lease Name: SKINNER D Well #: 6
County: BARBER Total Vertical Depth: 4918 feet

Operator License No.: 31142
Op Name: PETROLEUM PROPERTY SERVICES, IN
Address: 125 N MARKET SUITE 1251
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4850		WITH 2 SX CMT
PROD	5.5	4918	0	WITH 75 SX CMT
SURF	8.625	275		WITH 235 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/27/2017 3:00 PM
Plug Co. License No.: 34275 Plug Co. Name: SCOTT SERVICES LLC
Proposal Revd. from: KELLY SCHMEIDLER Company: PPSI Phone: (620) 546-4752

Proposed Plugging Method: SET CIBP @ 4850' IWHT 2 SX CMT. PLUG AT 990' WITH 12 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE
Date/Time Plugging Completed: 06/27/2017 6:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 4850' & BAILED 2 SX CMT THROUGH DUMP BAILER ON TOP OF CIBP. PERFORATE 5 1/2" CASING AT 990'. RUN TBG IN TO 987' & PUMPED DOWN TBG WITH 25 SX CMT/100# HULLS & 25 SX CMT. PULLED TBG OUT. PERFORATE 5 1/2" CASING AT 300'. RUN TBG IN TO 275' & PUMPED DOWN TBG WITH 120 SX CMT FILLING INSIDE & OUTSIDE OF 5 1/2" CASING WITH CMT TO SURFACE

Perfs:

Top	Bot	Thru	Comments
4887	4904		


INVOICED
AUG 29 2017

Remarks: USED COMMON CEMENT BY GLOBAL CEMENTING.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED
JUL - 7 2017
KCC DODGE CITY

