

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-16680-00-00
Spot: NWNENWSE Sec/Twnshp/Rge: 3-32S-15W
2548 feet from S Section Line, 1895 feet from E Section Line
Lease Name: SKINNER D Well #: 10
County: BARBER Total Vertical Depth: 4912 feet

Operator License No.: 31142
Op Name: PETROLEUM PROPERTY SERVICES, IN
Address: 125 N MARKET SUITE 1251
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4300		
LI	4.5	1201		SET W/PACKER STICK IN HOLE
PROD	5.5	4908	0	WITH 200 SX CMT
SURF	8.625	280		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/23/2017 1:00 PM
Plug Co. License No.: 34275 Plug Co. Name: SCOTT SERVICES LLC
Proposal Rcvd. from: KELLY SCHMEIDLER Company: EXCELL WIRELINE Phone: (620) 546-4752

Proposed Plugging Method: SAND BACK TO 4200' & 5 SX CMT. PERFORATE AT 990'. RUN TBG IN TO 990' PUMPED DOWN TBG WITH 25 SX CMT 100# HULLS & 25 SX CMT, DISPLACING FIRST 25 SX CMT OUT PERFS AT 990'. PERFORATE AT 330'. RUN TBG IN TO 330' & PUMP DOWN TBG WITH CMT FILLING 4 1/2" LINER & 5 1/2" X 4 1/2" CASING ANNULUSES TO SURFACE WITH CMT.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/26/2017 12:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4018' & PUT 5 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PERFORATE THROUGH 4 1/2" & 5 1/2" PIPE AT 990'. RUN TBG TO 990'. PUMP DOWN TBG WITH 25 SX CMT, 100# HULLS & 25 SX CMT, DISPLACING FIRST 25 SX CMT OUT PERFS AT 990'. SHUT DOWN. 6/26/17: TAG TOC @ 610'. PERFORATE AT 330'. RUNG TBG IN TO 330'. PUMPED DOWN TBG WITH 100 SX CMT. FILLED INSIDE OF 4 1/2" CASING & BACKSIDE OF 4 1/2" CASING. PERFS WERE NOT OPEN TO GET OUT & UP BACKSIDE OF 5 1/2" CASING. SHUT BACKSIDE & PRESSURED UP & BROKE OPEN PERFS. RESUME PUMPING CMT. HADN'T ESTABLISHED RETURNS UP BACKSIDE OF 5 1/2" CASING. LAID TBG DOWN. PUMPED DOWN 8 5/8" X 5 1/2" ANNULUS WITH 35 SX CMT. PRESSURED UP TO 250#. SHUT IN AT 200#. TOP OFF 4 1/2" CASING WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4245	4256		

Remarks: USED COMMON CEMENT BY GLOBAL OILFIELD SERVICES.

Plugged through: TBG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

SA

RECEIVED

JUN 28 2017

KCC DODGE CITY

MD

Form CP-2/3

INVOICED
AUG 29 2017