

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-20877-00-00
Spot: NENW Sec/Twnshp/Rge: 19-27S-15W
4759 feet from S Section Line, 3225 feet from E Section Line
Lease Name: WELLER UNIT C Well #: 3
County: PRATT Total Vertical Depth: 4640 feet

Operator License No.: 31142
Op Name: PETROLEUM PROPERTY SERVICES, IN
Address: 125 N MARKET SUITE 1251
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4618	1840	WITH 200 SX CMT
SURF	8.625	323		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/06/2017 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: RUN TBG IN TO TOP OF FISH & SPOT 100# HULLS & 30 SX CMT. PLUG AT 1000' WITH 10 SX GEL & 50 SX CMT. PLUG AT 350' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/06/2017 2:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

RUN TBG IN HOLE TO TOP OF FISH (FOUND AT 1875') & SPOT 100# HULLS & 30 SX CMT. 1ST PLUG AT 1000' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 35 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4413	4416		
4292	4295		
4172	4177		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE

Plugged through: CSG

INVOICED
AUG 29 2017

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

SA

RECEIVED
JUL 17 2017
KCC DODGE CITY