

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-007-21207-00-00
 Spot: SESWNWNE Sec/Twnshp/Rgc: 23-32S-12W
4244 feet from S Section Line, 2251 feet from E Section Line
 Lease Name: BLOOM Well #: 2
 County: BARBER Total Vertical Depth: 4790 feet

Operator License No.: 8653
 Op Name: PETROLEUM TECHNOLOGIES, INC.
 Address: 801 W 47TH ST STE 412
KANSAS CITY, MO 64112

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4060		WITH 2 SX CMT
CIBP		4270		
CIBP		4400		
CIBP		4650		
CIBP		4678		
CIBP		4700		
PROD	4.5	4785	2500	WITH 450 SX CMT
SURF	8.625	481		WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/26/2017 9:00 AM
 Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
 Proposal Revd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SET CIBP @ 4060' WITH 2 SX CMT. PLUG AT 750' WITH 10 SX GEL & 50 SX CMT. PLUG AT 510' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)
 Date/Time Plugging Completed: 07/26/2017 10:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4060' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 756' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 504' WITH 50 SX CMT. 3RD PLUG AT 62' WITH 40 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4706	4708		
4681	4683		
4673	4675		
4444	4448		
4319	4321		
4309	4311		
4103	4105		

INVOICED
 AUG 29 2017

Remarks: USED 60/40 POZMIX 4% GEL BY HURRICANE SERVICES.

Plugged through: TBG

District: 01

Signed Stephen J Pfeifer
 (TECHNICIAN)