

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-25958-00-00
Spot: S2N2SE Sec/Twnshp/Rgc: 12-16S-21W
1650 feet from S Section Line, 1450 feet from E Section Line
Lease Name: GOTTSCHALK Well #: 1
County: NESS Total Vertical Depth: 4238 feet

Operator License No.: 35414
Op Name: ROYAL ENERGY, INC.
Address: PO BOX 1820
DODGE CITY, KS 67801

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	208		WITH 150 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 07/27/2017 3:00 AM
Plug Co. License No.: 34743 Plug Co. Name: WHITE KNIGHT DRILLING LLC
Proposal Revd. from: TERRY AUSTIN Company: WHITE KNIGHT DRILLING LLC Phone: (785) 625-5155

Proposed Plugging Method: 1ST PLUG AT 1670' WITH 50 SX CMT. 2ND PLUG AT 960' WITH 80 SX CMT. 3RD PLUG AT 450' WITH 40 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE
Date/Time Plugging Completed: 07/27/2017 5:00 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

1ST PLUG AT 1670' WITH 50 SX CMT. 2ND PLUG AT 960' WITH 80 SX CMT. 3RD PLUG AT 450' WITH 40 SX CMT. 4TH PLUG AT 240' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY.

Plugged through: DP

District: 01

Signed

Michael Maier

(TECHNICIAN)

SA

RECEIVED
JUL 31 2017
KCC DODGE CITY

M

INVOICED
AUG 29 2017