

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-077-21901-01-00  
Spot: S2S2SWNW Sec/Twnshp/Rge: 7-35S-7W  
2440 feet from N Section Line, 660 feet from W Section Line  
Lease Name: MICHAEL 3507 Well #: 1-7H  
County: HARPER Total Vertical Depth: 5317 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	20	90		10 sx cement
	11 7	5317		290 sx cement
PROD	7	5317		290 SX
PROD	4.5	9953		385 sx cement
SURF	9.63	823		400 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/03/2017 12:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (405) 429-5610

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 08/07/2017 5:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

SET CIBP AT 4650', RELEASE BP @ CIRC 170 BBLs OF MUD. SPOT 50 SX CEMENT ON BP. RECOVER CASING FROM 1413 & PULLED FROM WELLBORE. RAN TUBING TO 1350' & SPOTTED 50 SKS CEMENT. PULLED TUBING TO 850' SPOTTED 50 SKS CEMENT. PULLED TUBING TO 310 & CIRCULATED CEMENT TO SURFACE WITH 105 SKS CEMENT.

Perfs:

Top	Bot	Thru	Comments
8409	8699		
8132	8358		
7280	7587		
6992	7222		
6576	6894		
6571	6894		

Remarks: ORR ENTERPRISES CLASS "C" CEMENT TMD = 9956

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

INVOICED  
AUG 29 2017