

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-033-21677-01-00
 Spot: SESESESE Sec/Twnshp/Rge: 26-31S-20W
252 feet from S Section Line, 179 feet from E Section Line
 Lease Name: HAROLD 3120 Well #: 2-26H
 County: COMANCHE Total Vertical Depth: 5107 feet

Operator License No.: 34192
 Op Name: SANDRIDGE EXPLORATION AND PRO
 Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4373		WITH 100 SX CMT
COND	20	90		WITH 15 SX CMT
	11 7	5536	1612	WITH 275 SX CMT
PROD	4.5	8787	0	WITH 450 SX CMT
SURF	9.625	957		WITH 550 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/26/2017 9:30 AM
 Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
 Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 4373' WITH 100 SX CMT. PLUG AT 970' WITH 70 SX CMT. PLUG AT 290' WITH 50 SX CMT. PLUG AT 64' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: PARTIAL
 Date/Time Plugging Completed: 06/26/2017 11:50 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

6/22/17: SET CIBP @ 4373'. CIRCULATE 160 BBL THEN SPOTTED 100 SX CMT ON TOP OF CIBP. 6/23/17: CUT & LAID DOWN 1612' OF 7" CASING. 6/26/17: 1ST PLUG AT 970' WITH 70 SX CMT. 2ND PLUG AT 290' WITH 50 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
8787	8797		
8331	8632		
7824	8210		
7338	7692		
6975	7244		
6604	6872		
6121	6512		
5794	6080		
5382	5632		

INVOICED
 AUG 29 2017

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES. TMD= 9464'.

Plugged through: TBG

District: 01

RECEIVED
 JUL - 7 2017
 KCC DODGE CITY

Signed [Signature]
 (TECHNICIAN)