

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-165-21472-00-00
Spot: NENENW Sec/Twship/Rge: 10-18S-17W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease Name: HARDY B Well #: 1
County: RUSH Total Vertical Depth: 3622 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>34278</u>	<u>PROD</u>	<u>4.5</u>	<u>3622</u>	<u>0</u>	<u>WITH 150 SX CMT</u>
Op Name: <u>SHAWN D. EVANS INC. DBA ACE OIL C</u>	<u>SURF</u>	<u>7</u>	<u>1173</u>		<u>WITH 350 SX CMT</u>
Address: <u>18529 WALTERS RD PO BOX 606</u> <u>RUSSELL, KS 67665</u>					

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/30/2017 10:30 AM
Plug Co. License No.: 34946 Plug Co. Name: ACE WELL SERVICE, INC.
Proposal Revd. from: DALTON POPP Company: ACE WELL SERVICE, INC. Phone: (620) 200-1812

Proposed Plugging Method: AS PER KCC NOTE: CEMENT AMOUNTS FOR SURFACE & PRODUCTION CSG WERE EST FROM OTHER WELLS IN THE CLOSE AREA. NO RECORDS FOUND ON ACTUAL AMOUNTS. SQUEEZE PERFS WITH 25 SX CMT & 100# HULLS. PERFORATE AT 1230' WITH 12 SX GEL, 50 SX CMT WITH HULLS IN LAST 25 SX CMT. PERFORATE AT 450' WITH CMT TO 0'.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: NONE
Date/Time Plugging Completed: 06/30/2017 1:20 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

AT 3588' PUMPED 25 SX CMT WITH 100# HULLS. PERFORATE AT 1261' WITH 12 SX GEL & 50 SX CMT & 200# HULLS IN LAST 25 SX CMT. PERFORATE AT 460' & PUMP 110 SX CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
3600	3602		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENT.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

518

RECEIVED
JUL - 7 2017
KCC DODGE CITY



INVOICED
AUG 29 2017