

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-04308-00-00  
Spot: SWNWSW Sec/Twnshp/Rge: 8-18S-13W  
1650 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: RIEDEL Well #: 7  
County: BARTON Total Vertical Depth: 3310 feet

Operator License No.: 34278  
Op Name: SHAWN D. EVANS INC. DBA ACE OIL C  
Address: 18529 WALTERS RD PO BOX 606  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3309		100 SX
SURF	8.625	763		350 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/29/2017 8:00 AM  
Plug Co. License No.: 34946 Plug Co. Name: ACE WELL SERVICE, INC.  
Proposal Rcvd. from: SHAWN EVANS Company: SHAWN D. EVANS INC. DBA ACE Phone: (785) 324-0502

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls and 13 sx gel.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/29/2017 2:00 PM KCC Agent: BRUCE RODIE

**Actual Plugging Report:**

Perforated at 1400' and 750'. Pumped water first and tubing pressured up to 800 psi. Decided to pump cement first. Ran tubing to 3091' and pumped 40 sx cement w/100 # hulls. Pulled tubing to 2691' and pumped 13 sx gel followed by 10 sx cement. Pulled tubing to 1400' and pumped 65 sx cement. Pulled tubing to 750'. Circulated cement to surface with 55 sx cement. Shut valve on casing and circulated cement to surface on surface pipe with 95 sx cement. Pulled tubing and topped off with 10 sx cement.

GPS: 38.49685 -09879231

Perfs:

Remarks: QUALITY OILWELL CEMENTING

Plugged through: TBG

District: 04

Signed Bruce Rodie

(TECHNICIAN)

CM

KCC WICHITA

JUL 20 2017

RECEIVED

JUL 05 2017

Form CP-2/3

INVOICED  
AUG 29 2017