

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-009-04306-00-00  
Spot: SESESW Sec/Twnshp/Rge: 8-18S-13W  
330 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: RIEDEL Well #: 5  
County: BARTON Total Vertical Depth: 3303 feet

Operator License No.: 34278  
Op Name: SHAWN D. EVANS INC. DBA ACE OIL C  
Address: 18529 WALTERS RD PO BOX 606  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3302		100 SX
SURF	8.625	750		350 SX

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/28/2017 8:00 AM  
Plug Co. License No.: 34946 Plug Co. Name: ACE WELL SERVICE, INC.  
Proposal Rcvd. from: SHAWN EVANS Company: SHAWN D. EVANS INC. DBA ACE Phone: (785) 324-0502

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
Well has been squeezed at 2800'

Plugging Proposal Received By: BRUCE RODIE  
Date/Time Plugging Completed: 06/28/2017 2:00 PM

WitnessType: COMPLETE (100%)  
KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Perforated at 1400' and 750'. Ran sand pump to 2350' and stacked out. Ran tubing to 2350'. Tried to circulate tubing down and got to 2361'. Stacked out and decided to plug from 2361'. Ran tubing to 2350' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 1400' and pumped 65 sx cement. Pulled tubing to 750'. Circulated cement to surface with 85 sx cement. Shut valve on casing and circulated cement to surface on surface pipe with 70 sx cement. Pulled tubing and topped off with 5 sx cement.

GPS: 38.49358 -098.78544

Remarks: QUALITY OILWELL CEMENTING

Plugged through: TBG

District: 04

Signed

*Bruce Rodie*

KCC WICHITA

(TECHNICIAN)

CM

JUL 05 2017

JUL 20 2017

RECEIVED

Form CP-2/3

INVOICED  
AUG 29 2017