

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-151-22404-00-00  
Spot: NWSESESW Sec/Twnshp/Rge: 20-27S-12W  
348 feet from S Section Line, 2076 feet from W Section Line  
Lense Name: BOGART Well #: #1  
County: PRATT Total Vertical Depth: 4325 feet

Operator License No.: 3959  
Op Name: SIROKY OIL MANAGEMENT  
Address: PO BOX 464  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3990		WITH 2 SX CMT
CIBP		4140		
PROD	5.5	4317	1718	WITH 150 SX CMT
SURF	10.75	288		WITH 300 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/03/2017 8:00 AM  
Plug Co. License No.: 34484 Plug Co. Name: FOSSIL DRILLING, INC.  
Proposal Rcvd. from: SPENCER SIROKY Company: FOSSIL DRILLING, INC. Phone: (620) 672-5625

Proposed Plugging Method: SET CIBP @ 3900' & 2 SX CMT. PLUG AT 700' WITH 12 SX GEL & 50 SX CMT. PLUG AT 300' WITH 60 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/03/2017 9:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3990' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 704' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 326' WITH 60 SX CMT. 3RD PLUG AT 40' WITH 35 SX CMT. LAID DOWN LAST JOINT. TOP OFF 10 3/4" WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4206	4236		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer  
SA (TECHNICIAN)

RECEIVED  
AUG - 4 2017  
KCC DODGE CITY

INVOICED  
AUG 29 2017