

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-151-22390-00-00  
Spot: SENWSWSE Sec/Twnshp/Rge: 20-27S-12W  
683 feet from S Section Line, 2301 feet from E Section Line  
Lease Name: KOVACH Well #: 1  
County: PRATT Total Vertical Depth: 4500 feet

Operator License No.: 3959  
Op Name: SIROKY OIL MANAGEMENT  
Address: PO BOX 464  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4100		WITH 5 SX CMT
PROD	5.5	4478	720	WITH 150 SX CMT
SURF	10.75	239		WITH 275 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/01/2017 8:00 AM  
Plug Co. License No.: 34484 Plug Co. Name: FOSSIL DRILLING, INC.  
Proposal Rcvd. from: BRIAN SIROKY Company: SIROKY OIL MANAGEMENT Phone: (620) 672-5625

Proposed Plugging Method: SET CIBP @ 4100' & 2 SX CMT. PLUG AT 630' WITH 10 SX GEL & 50 SX CMT. PLUG AT 280' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/01/2017 10:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4100' & PUT 5 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 624' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 282' WITH 70 SX CMT. 3RD PLUG AT 60' WITH 40 SX CMT. LAID TBG DOWN & TOP WELL OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4157	4212		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: TBG

INVOICED  
AUG 29 7017

District: 01

Signed Stephen J Pfeifer  
(TECHNICIAN)

SA

RECEIVED  
AUG - 4 2017  
KCC DODGE CITY