

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-055-00159-00-00  
Spot: SW Sec/Twship/Rge: 20-21S-32W  
1320 feet from S Section Line, 1320 feet from W Section Line  
Lease Name: ARCHER UT Well #: 1  
County: FINNEY Total Vertical Depth: 2763 feet

Operator License No.: <u>6044</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>STELBAR OIL CORPORATION, INC.</u>	CIBP		2590		WITH 2 SX CMT
Address: <u>1625 N WATERFRONT PKWY SUITE 2</u>	PROD	4.5	2763	0	WITH 150 SX CMT
<u>WICHITA, KS 67206</u>	SURF	8.625	319		WITH 275 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/19/2017 1:00 PM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: TY LUNN Company: STELBAR OIL CORPORATION Phone: (316) 264-8378

Proposed Plugging Method: CIBP @ 2590' WITH 2 SX CMT. PLUG AT 2050' WITH 25 SX CMT. PLUG AT 1150-60' WITH 40 SX CMT. TOOH WITH TBG. PERFORATE AT 350' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK WitnessType: NONE  
Date/Time Plugging Completed: 07/19/2017 6:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2590' WITH 2 SX CMT. LOAD CASING WITH WATER & RUN CBL. FOUND TOC @ 674'. PLUG AT 2041' WITH 25 SX CMT. PLUG AT 1144' WITH 40 SX CMT. PERFORATE 4 HOLES AT 350' & CIRCULATE CMT TO SURFACE USING 112 SX CMT LEAVING THE 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2682	2688		
2659	2669		
2630	2640		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: TBG

District: 01

Signed

*Ken Jehlik*  
5A

(TECHNICIAN)

INVOICED  
AUG 29 2017

RECEIVED  
JUL 27 2017  
KCC DODGE CITY

Form CP-2/3