

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-055-10032-00-00  
Spot: NWNWSENE Sec/Twship/Rge: 19-21S-32W  
3926 feet from S Section Line, 1218 feet from E Section Line  
Lease Name: GOSSMAN Well #: 1-19  
County: FINNEY Total Vertical Depth: 2701 feet

Operator License No.: 6044  
Op Name: STELBAR OIL CORPORATION, INC.  
Address: 1625 N WATERFRONT PKWY SUITE 2  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2600		WITH 2 SX CMT
PROD	4.5	2701	0	WITH 75 SX CMT
SURF	7	358		WITH 150 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/18/2017 8:00 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: TY LUNN Company: STELBAR OIL CORPORATION Phone: (316) 264-8378

Proposed Plugging Method: CIBP @ 2600' WITH 2 SX CMT. LOAD & TEST CASING TO 300#. RUN CBL. PERFORATE 4 HOLES AT 1100'. INJECTION RATE 2 BPM @ 350 PSI. ISIP-0. PUMP 30 SX CMT, DROP BALL SEALERS THEN 30 SX CMT DOWN CASING. DISPLACE WITH WATER TO PRESSURE SHUT OFF. PERFORATE 4 HOLES @ 375'. CIRCULATE CMT TO SURFACE THROUGH PERFS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/18/2017 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2600' WITH 2 SX CMT. LOAD HOLE & TEST CASING TO 300#. RUN CBL. TOC ON PRIMARY CMT JOB IS 2230'. ADDITIONAL REMEDIAL CMT FOUND FROM 1790' TO 1544'. POSSIBLE CMT STRINGERS ABOVE THIS BUT DETERMINATION IS INCONCLUSIVE. PERFORATE 4 HOLES AT 1100'. INJECTION RATE DOWN CASING 2 BPM @ 350 PSI. PUMP 30 SX CMT, DROP 15 BALL SEALERS, THEN PUMP 30 SX CMT. DISPLACE TO 650' AT 400 PSI, LEAVING 30 SX CMT OUTSIDE THE 4 1/2" CASING & 30 SX CMT INSIDE THE 4 1/2" CASING. PERFORATE 4 HOLES AT 375' & CIRCULATE CMT TO SURFACE WITH 90 SX CMT LEAVING THE CASING & ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2664	2690		
2634	2640		


Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: CSG

INVOICED  
AUG 29 2017

District: 01

Signed



(TECHNICIAN)

RECEIVED  
JUL 21 2017  
KCC DODGE CITY