

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-055-00184-00-00  
Spot: NW Sec/Township/Rge: 23-21S-33W  
1320 feet from N Section Line, 1320 feet from W Section Line  
Lease Name: DUNN Well #: 1  
County: FINNEY Total Vertical Depth: 2687 feet

Operator License No.: 6044  
Op Name: STELBAR OIL CORPORATION, INC.  
Address: 1625 N WATERFRONT PKWY SUITE 2  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2625		WITH 2 SX CMT
PROD	4.5	2687	0	WITH 100 SX CMT
SURF	7	356		WITH 100 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/18/2017 11:00 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: TY LUNN Company: STELBAR OIL COPORATION Phone: (316) 264-8378

Proposed Plugging Method: CIBP AT 2625' WITH 2 SX CMT. LOAD & TEST CASING. RUN CBL. PERFORATE 4 HOLES AT 380'. ESTABLISH INJECTION RATE THROUGH PERFS VIA CASING. RUN TBG TO 2100' & SPOT 25 SX CMT PLUG. PULL TO 1200' & SPOT 40 SX CMT PLUG. LAY DOWN TBG. HOOK UP TO CASING. CIRCULATE CMT TO SURFACE THROUGH PERFS LEAVING 4 1/2" CASING & 4 1/2" X 7" ANNULUS FULL OF CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/18/2017 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP AT 2625' WITH 2 SX CMT. LOAD CASING WITH WATER. RAN CBL. TOC APPROX. 620'. PERFORATE 4 HOLES AT 380'. RUN TBG TO 2087' & SPOT 25 SX CMT. PUMP 40 SX CMT AT 1198'. TOOH WITH TBG. CIRCULATE CMT TO SURFACE THROUGH PERFS AT 380' LEAVING THE 4 1/2" CASING & 4 1/2" X 7" ANNULUS FULL OF CMT USING 80 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2653	2679		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: TBG

District: 01

Signed

  
(TECHNICIAN)

RECEIVED  
JUL 25 2017  
KCC DODGE CITY

Form CP-2/3

INVOICED  
AUG 29 2017