

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-179-21436-00-00  
Spot: SWSEENENW Sec/Twnshp/Rge: 20-6S-28W  
993 feet from N Section Line, 1989 feet from W Section Line  
Lease Name: LUCKY SEVENS LLC Well #: 1-20  
County: SHERIDAN Total Vertical Depth: 4500 feet

Operator License No.: 35245  
Op Name: SUEMAUR EXPLORATION & PRODUCT  
Address: 539 N. CARANCAHUA SUITE 1100  
CORPUS CHRISTI, TX 78401

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	261		240 SX

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/11/2017 12:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JUAN Company: MURFIN DRILLING CO., INC. Phone: (620) 655-6886

Proposed Plugging Method: Ordered 260 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE  
Date/Time Plugging Completed: 06/11/2017 6:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st plug @2525 w/50 sx  
2nd plug @1750 w/100 sx  
3rd plug @300 w/50 sx  
4th plug @40 w/10 sx  
  
Rathole 30 sx Mousehole 20 sx

Perfs:

Remarks: BJ SERVICES

Plugged through: DP

INVOICED  
AUG 29 2017

District: 04

KCC WICHITA

JUL 20 2017

RECEIVED

*Case Morris*  
(TECHNICIAN)

JUN 15 2017