

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-01403-00-02
Spot: NWNEENW Sec/Twnshp/Rge: 11-12S-23W
4989 feet from S Section Line, 3020 feet from E Section Line
Lease Name: HIXSON B Well #: 1
County: TREGO Total Vertical Depth: 3738 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3732		125 SX
SURF	8.625	227		175 SX

Well Type: SWD UIC Docket No: D27802.0 Date/Time to Plug: 06/08/2017 10:30 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: TERRY Company: BEAR PETROLEUM, LLC Phone: (316) 524-1225

Proposed Plugging Method: Ordered 330 sx 60/40 pozmix 4% gel cement w/500 # hulls and 11 sx gel.
Perforations: 3701' - 3717'.
DV Tool at 1860'. CWC amount unknown.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/14/2017 11:30 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3584' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2284' and pumped 100 sx cement. Pulled tubing to 1084' and pumped 200 sx cement w/250 # hulls. No circulation of cement. Pulled tubing out.
06/09/2017- Ran tubing back in and tagged cement at 904'. Pumped 150 sx cement. Good circulation of cement. Pulled tubing out and topped off casing with 15 sx cement. Tied on to backside and squeezed with 10 sx cement. Shut in pressure 200 psi.

GPS: 39.02919 -099.84476

Perfs:


Top	Bot	Thru	Comments
3715	3717		
3701	3717		

Remarks: COPELAND CEMENT TICKET # 45132

Plugged through: TBG

District: 04

Signed


(TECHNICIAN)

CM

KCC WICHITA

JUL 20 2017

RECEIVED

INVOICED
AUG 22 2017