

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-135-23062-00-01
Spot: SENEWSWE Sec/Township/Rge: 3-17S-21W
903 feet from S Section Line, 1616 feet from E Section Line
Lease Name: THOMPSON A Well #: 2
County: NESS Total Vertical Depth: 4210 feet

Operator License No.: 34318

Op Name: BEREXCO LLC

Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT	5.5	1489		WITH 400 SX CMT
PROD	5.5	4208	0	WITH 150 SX CMT
SURF	8.625	423		WITH 250 SX CMT

Well Type: EOR

UIC Docket No: E27640.0

Date/Time to Plug: 06/30/2017 10:00 AM

Plug Co. License No.: 34318

Plug Co. Name: BEREXCO LLC

Proposal Rcvd. from: MARK LEIKER

Company: BEREXCO LLC

Phone: (316) 772-8649

Proposed Plugging Method: PUMP BOTTOM WITH 50 SX CMT & 100# HULLS. PERFORATE AT 1500' & CIRCULATE CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 06/30/2017 1:00 PM

KCC Agent: LARRY HARRIS

Actual Plugging Report:

Perfs:

RAN TBG & TAGGED AT 3554'. PUMPED 50 SX CMT WITH 100# HULLS. HELD AT 900 PSI. PULLED TBG TO 1497' & CIRCULATE CMT TO SURFACE WITH 135 SX CMT. PULLED TBG & TOPPED OFF WITH 15 SX CMT. TIED ON TO ANNULUS & PRESSURED TO 1000 PSI. NO CMT.

Top	Bot	Thru	Comments
3524	3590		

INVOICED
AUG 22 2017

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY GLOBAL CEMENTING.

Plugged through: TBG

District: 01

Signed Larry Harris (TECHNICIAN)

RECEIVED
JUL - 7 2017
KCC DODGE CITY