

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-23065-00-00  
Spot: SENENW Sec/Twnshp/Rge: 22-32S-4E  
4290 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: CULLEN TURNER Well #: 1  
County: COWLEY Total Vertical Depth: 3333 feet

Operator License No.: <u>4419</u>	String	Size	Depth (ft)	Pulled (ft)	Comments
Op Name: <u>BEAR PETROLEUM, LLC</u>	CIBP		2580		
Address: <u>PO BOX 438</u>	PROD	5.5	3331		150 SX
<u>HAYSVILLE, KS 67060</u>	SURF	8.625	200		200 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/29/2017 8:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: R. A. (DICK) SCHREMMER Company: GRESSEL OILFIELD SERVICE Phone: (316) 524-1225

Proposed Plugging Method: AS PER KCC RULES & REGS/ CIBP @ 2300' W/ 5 SXS PERF & CIRCUALTE 250'-0'.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: NONE  
Date/Time Plugging Completed: 06/29/2017 5:45 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

CIBP SET @ 2316' W/ 2 SXS CEMENT ON TOP OF PLUG. PERFORATED SQUEEZE HOLES @ 250-251' 4 HOLES. RIH W/ TUBING @ 260', COPELAND ACID CIRCULATED & PUMPED 95 SXS 60/40 POZMIX 4% GEL 2% CC TO SURFACE. CEMENT CIRCUALTED. CEMENT TICKET #44913.

Perfs:

Top	Bot	Thru	Comments
2522	2530		
2310	2326		

INVOICED  
AUG 2 2 2017

Remarks:

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

JK