

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-01168-00-00

Spot: NESWNE

Sec/Twnshp/Rge: 9-28S-15E

4570 feet from S Section Line, 940 feet from E Section Line

Lease Name: PIERPOINT

Well #: W 4

County: WILSON

Total Vertical Depth: 1090 feet

Operator License No.: 33756

Op Name: DAVIS, JOHN T. DBA TURTLE OIL CO

Address: 1229 HWY 54

YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comment
--------	------	------------	-------------	---------

PROD	4.5	1090		110 SX
------	-----	------	--	--------

SURF	7	40		10 SX
------	---	----	--	-------

Well Type: EOR

UIC Docket No: E11290.4

Date/Time to Plug: 07/11/2017 8:00 AM

Plug Co. License No.: 33900

Plug Co. Name: LEIS, STEVEN A.

Proposal Rcvd. from: TOM DAVIS

Company: LEIS, STEVEN A.

Phone: (620) 496-6822

Proposed Plugging Method: Stage PlugsSet a 50ft plug at 5ft below the perfsSet a 50ft plug at the BKCSSet a plug from 250ft to surface

Plugging Proposal Received By: JOHN ALMOND

WitnessType: NONE

Date/Time Plugging Completed: 07/14/2017 9:00 AM

KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

According to operator a cement string was lowered to 970 ft and 7 sacks of cement spotted. The cement string was pulled to 550 ft and 7 sacks of cement spotted. The cement string was pulled to 250 ft and the well filled to surface with 21 sacks of cement. A total of 35 sacks of portland cement were used to plug well.

RECEIVED
KCC DIST #3
JUL 18 2017
CHANUTE, KS

AD

INVOICED

AUG 24 2017

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning
(TECHNICIAN)