

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-20195-00-01
Spot: E2NWNENW Sec/Township/Rge: 26-16S-29W
4950 feet from S Section Line, 3606 feet from E Section Line
Lease Name: JAMES Well #: 1
County: LANE Total Vertical Depth: 4330 feet

Operator License No.: 6170
Op Name: GLOBE OPERATING, INC.
Address: PO BOX 12
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2100		
PROD	5.5	4330	0	WITH 125 SX CMT
SURF	8.625	325		WITH 225 SX CMT

Well Type: SWD UIC Docket No: D19498.0 Date/Time to Plug: 07/17/2017 11:45 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Revd. from: JEFF WERTH Company: H-D OILFIELD SERVICE, INC. Phone: (785) 798-7677

Proposed Plugging Method: PUMP CMT TOP TO BOTTOM WITH HULLS. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/17/2017 1:40 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

TOOK INJECTION RATE OF 2 1/2 BBL A MINUTE AT 500#. PUMPED 210 SX CMT & 300# HULLS. CASING PRESSURED TO 1000#. SHUT IN WITH 800#. TIED ONTO BACKSIDE & PUMPED 140 SX CMT DOWN BACKSIDE. PRESSURED TO 300#.

Top	Bot	Thru	Comments
1900	1940		

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

Signed Michael Maier
(TECHNICIAN)

RECEIVED
JUL 18 2017
KCC DODGE CITY

5/A

Form CP-2/3

INVOICED
AUG 29 2017