

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-22639-00-00
Spot: NWSENNWNW Sec/Twnshp/Rge: 7-33S-2E
825 feet from N Section Line, 865 feet from W Section Line
Lease Name: FOUR J (HOMER) Well #: 7-11 SWD
County: SUMNER Total Vertical Depth: 4350 feet

Operator License No.: 35032
Op Name: K3 OIL & GAS OPERATING COMPANY
Address: 24900 PITKIN RD SUITE 305
THE WOODLANDS, TX 77386

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		3780		
PROD	8.75	3841		300 SX
SURF	9.625	308		165 SX
T1	3.5	3780		

Well Type: SWD UIC Docket No: D31121.0 Date/Time to Plug: 08/01/2017 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: JOHN RIGAS Company: K3 OIL & GAS OPERATING COMP Phone: (832) 813-8496

Proposed Plugging Method: As per KCC instructions and requirements

Plugging Proposal Received By: DAN FOX Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/25/2017 12:00 PM KCC Agent: JONATHAN HILL

Actual Plugging Report:

Perfs:

- 1) Excel Wireline ran in hole and set CIBP @ 3700' and capped w/ 7 sks cement
- 2) Ran back in hole w/ wireline and perforated at 360'
- 3) Ran in hole w/ poly-line coiled tubing to 365', loaded hole w/ water
- 4) Pumped 145 sks of 60/40/2% cement (no additives). Cement circulated up backside. Shut in backside, cement circulated up 7" casing.
- 5) Pulled coiled tubing out, topped off well w/ cement. Hole staying full

Remarks: CEMENTING COMPLETED BY GRESSEL OILFIELD SERVICE. TICKET # 44922

Plugged through: TBG

District: 02

Signed Jonathan Hill
(TECHNICIAN)

INVOICED
AUG 29 2017

18