

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-001-30405-00-00  
Spot: NWSESENE Sec/Twnshp/Rge: 34-23S-21E  
2990 feet from S Section Line, 602 feet from E Section Line  
Lease Name: WHITCOMB Well #: 3-1  
County: ALLEN Total Vertical Depth: 625 feet

Operator License No.: <u>3728</u>	String	Size	Depth (ft)	Pulled (ft)	Comment
Op Name: <u>RJ ENERGY, LLC</u>	PROD	2.875	619		60 SX
Address: <u>22082 NE NEOSHO RD</u> <u>GARNETT, KS 66032</u>	SURF	7	20		5 SX

Well Type: EOR UIC Docket No: E18614.34 Date/Time to Plug: 07/10/2017 12:00 AM  
Plug Co. License No.: 3728 Plug Co. Name: RJ ENERGY, LLC  
Proposal Revd. from: JASON KENT Company: RJ ENERGY, LLC Phone: (785) 448-4101

Proposed Plugging Method: Run down well and pump well full.

Plugging Proposal Received By: RYAN DULING Witness Type: NONE  
Date/Time Plugging Completed: 07/10/2017 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the inside of the 2.875" that was cemented inside the 7" surface casing. Pumped and circulated cement through the 1" pipe inside the 2.875" casing from 600' to surface. Pulled the 1" pipe out of the casing and topped the well off with cement. A total of 18 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
576	586		RECEIVED KCC DIST # 3 AUG 08 2017 CHANUTE, KS RD

INVOICED  
AUG 29 2017

Remarks: PLUGGED DUE TO A FAILED MIT.

Plugged through: TBG

District: 03

Signed [Signature] E.C.A.S.  
(TECHNICIAN)