

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-159-22716-00-00  
Spot: NWNESENE Sec/Twnshp/Rge: 19-21S-6W  
1460 feet from N Section Line, 430 feet from E Section Line  
Lease Name: HEDRICK 2106 Well #: 19-1  
County: RICE Total Vertical Depth: 4568 feet

Operator License No.: 35053  
Op Name: TAPSTONE ENERGY, LLC  
Address: PO BOX 1608  
OKLAHOMA CITY, OK 73101

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	7	3992		
COND	18	63		20 SX
	11	7		462 sx cement
	11	7		462 SX
PROD	7	3984		462 SX
SURF	9.625	378		270 SX

Well Type: SWD UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/29/2017 12:30 PM  
Plug Co. License No.: 35086 Plug Co. Name: SJL WELL SERVICE, LLC  
Proposal Rcvd. from: BOONE DAVIDSON Company: TAPSTONE ENERGY LLC Phone: (620) 896-7200

Proposed Plugging Method: CIBP @ 3934' CAPPED WITH 25 SX'S CEMENT. CUT 7" CASING AT 950' AND PULL OUT. RUN IN TUBING TO 1050' AND PUMP 100 SX'S, PULL OUT AND TAG. RUN TUBING BACK INTO 450' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. MIT FOR TA DONE IN 2014, CIBP WAS SET IN 2-2014.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: PARTIAL  
Date/Time Plugging Completed: 06/29/2017 3:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, TAG CIBP AT 3992'. RUN CEMENT BOND LOG TO DETERMINE TOC, FOUND TO BE ALL THE WAY UP TO SURFACE. RUN TUBING TO 3980' AND PUMPED 25 SX'S COMMON CEMENT ON TOP OF CIBP. PULL TUBING TO 1150' AND PUMPED 235 SX'S CEMENT AND CIRCULATED CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. TOP OFF RAT HOLE ALSO. CUT OFF WELL-HEAD AND WELDED PLATE ON TOP OF CASING THAT LABELED WELL.

Perfs:

Remarks: DENIED TA WELL. BASIC SERVICE #15124

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

INVOICED  
AUG 29 2017

SK