

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-049-21607-00-01  
Spot: NESWNW Sec/Twnshp/Rge: 27-29S-9E  
3774 feet from S Section Line, 4423 feet from E Section Line  
Lease Name: DAVES Well #: D20  
County: ELK Total Vertical Depth: 2379 feet

Operator License No.: 32874  
Op Name: VEEM JADE OIL & GAS LLC  
Address: 11417 S GRANITE AVE  
TULSA, OK 74137

| String | Size  | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD   | 4.5   | 2379       |             |         |
| SURF   | 7     | 59         |             |         |
| T1     | 2.375 | 2284       |             |         |

Well Type: EOR UIC Docket No: E31234.1 Date/Time to Plug: 07/12/2017 12:00 PM

Plug Co. License No.: 99973 Plug Co. Name: ELITE CEMENTING AND ACID SERVICE, LLC

Proposal Rcvd. from: KEVIN MCCOY Company: Phone:

Proposed Plugging Method: Run 1" to TD and circulate cement to surface.

Plugging Proposal Received By: LARRY MARCHANT

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 07/12/2017 12:00 PM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

This well had 2 3/8" liner cemented in the 4 1/2" casing. Washed 1" to TD. Lost circulation. Pulled 1". Hooked onto casing and squeezed 70 sackd of 60/40 pozmix with 4% gel and cotton scad hulls down casing. Shut well in with 550 psi on casing.

RECEIVED  
KCC DIST # 3  
AUG 08 2017  
CHANUTE, KS

DS  
INVOICED  
AUG 29 2017

Remarks: WELL WAS PLUGGED BECAUSE WELL WOULD NOT PASS MIT.

Plugged through: CSG

District: 03

Signed DALS

(TECHNICIAN)