

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-063-21125-00-00  
Spot: W2SWSWNE Sec/Twnshp/Rge: 11-15S-29W  
2970 feet from S Section Line, 2410 feet from E Section Line  
Lease Name: MALANCO Well #: 2  
County: GOVE Total Vertical Depth: 4350 feet

Operator License No.: 32457  
Op Name: ABERCROMBIE ENERGY, LLC  
Address: 10209 W. CENTRAL, STE 2  
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4324		260 SX
SURF	8.625	414		255 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/11/2017 9:30 AM  
Plug Co. License No.: 6454 Plug Co. Name: CHEYENNE WELL SERVICE, INC.  
Proposal Rcvd. from: TIM JULIAN Company: ABERCROMBIE ENERGY, LLC DB Phone: (620) 793-8186

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.  
DV Tool at 1356' w/400 sx cement.  
Perforations: 3928' - 3930'  
Tubing stuck in hole cut off at 2510'

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/11/2017 4:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 2510'. Pumped 200 sx cement w/300 # hulls. Pulled tubing to 1700' and pumped 250 sx cement w/200 # hulls. Cement circulated. Pulled tubing out. Topped off with 35 sx cement. Tied on to backside and squeezed with 20 sx cement. Shut in pressure 400 psi.

GPS: 38.76599 -100.51131

Perfs:

Top	Bot	Thru	Comments
3928	3930		

Remarks: QES CEMENT TICKET # 53534

Plugged through: TBG

INVOICED  
AUG 01 2017

District: 04

Signed \_\_\_\_\_

*(Signature)*  
(TECHNICIAN)

CM

KCC WICHITA

JUL 20 2017

RECEIVED

JUL 12 2017