

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-075-00022-00-01  
Spot: SESENWSE Sec/Twnshp/Rge: 20-26S-40W  
1360 feet from S Section Line, 1330 feet from E Section Line  
Lease Name: MCCARTY OWWO Well #: 1  
County: HAMILTON Total Vertical Depth: 5544 feet

Operator License No.: 32457  
Op Name: ABERCROMBIE ENERGY, LLC  
Address: 10209 W. CENTRAL, STE 2  
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2350		WITH 2 SX CMT
CIBP		2590		
PROD	5.5	3060	0	WITH 420 SX CMT
SURF	8.625	1893		WITH 825 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/18/2017 9:30 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: TIM JULIAN Company: ABERCROMBIE ENERGY Phone: (620) 793-8186

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/18/2017 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2350' WITH 2 SX CMT. PUMP 20 SX CMT AT 1950' THROUGH TBG.  
PERFORATE 4 HOLES AT 750'. CIRCULATE CMT TO SURFACE THROUGH PERFS  
LEAVING THE 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS FULL OF CMT USING 230  
SX CMT.

Perfs:


Top	Bot	Thru	Comments
2598	2662		
2535	2555		
2475	2478		
2404	2410		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

INVOICED  
AUG 01 2017

Plugged through: TBG

District: 01

Signed   
(TECHNICIAN)  
5A

RECEIVED  
JUL 25 2017  
KCC DODGE CITY 