

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-20833-00-00
Spot: SWNENWNE Sec/Twnshp/Rge: 8-33S-6E
4922 feet from S Section Line, 1932 feet from E Section Line
Lease Name: SHENEMAN Well #: 1
County: COWLEY Total Vertical Depth: 3180 feet

Operator License No.: 33405
Op Name: ANSTINE & MUSGROVE INC.
Address: PO BOX 391
PONCA CITY, OK 74602

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3178		150 SX
SURF	8.625	203		135 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/25/2017 8:00 AM
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.
Proposal Rcvd. from: GARY ANSTINE Company: ANSTINE & MUSGROVE INC. Phone: (620) 441-8165

Proposed Plugging Method: AS PER KCC RULES & REGS / CIBP @ 3090 W/25 SXS PERF & CIRCULATE 350'-0;

Plugging Proposal Received By: B. J. HOPE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/26/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH W/TUBING @ 3006', QES ESTABLISHED CIRCULATION. MIXED & PUMPED 35 SXS 60/40 POZMIX 4% GEL W/100# HULLS & DISPLACED IN CASING. LAYED TUBING DOWN. TAGGED CEMENT PLUG @ 2504'. PERFORATED SQUEEZE HOLES 350' -351' (4 SHOTS) RIH W/TUBING @ 352', QES ESTABLISHED CIRCULATION, MIXED & PUMPED 35 SXS 60/40 POZMIX TO SURFACE. CLOSED VALVE & PUMPED 125 SXS ON BACKSIDE OF 4 1/2" CASING. CEMENT CIRCULATED. TICKET #53344. TOTAL 160 SXS. P&A COMPLETE.

Top	Bot	Thru	Comments
3109	3116	CSG	

Remarks:

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
(TECHNICIAN)

INVOICED

AUG 01 2017