

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-25449-00-00

Spot: SENWNENW

Sec/Twnshp/Rge: 29-30S-17E

4946 feet from S Section Line, 3568 feet from E Section Line

Lease Name: SML

Well #: 3

County: WILSON

Total Vertical Depth: 862 feet

Operator License No.: 34769

Op Name: CHEROKEENRG LLC

Address: 112 SOUTH 5TH STREET P.O. BOX 111
NEODESHA, KS 66757

String Size Depth (ft) Pulled (ft) Comment

PROD 4.5 850 138 SX

SURF 8.625 21 4 SX

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 06/29/2017 8:00 AM

Plug Co. License No.: 31696

Plug Co. Name: CUNNINGHAM CRUDE, A GENERAL PARTNERSHIP

Proposal Revd. from: PAM SCHULTZ

Company: CHEROKEE NRG LLC

Phone: (620) 432-1840

Proposed

Plugging

Method:

Pull rod and tubing out of hole, run tubing to bottom, gel hole, spot 50' plug (5 sacks), pull up to 500', spot 50' plug (5 sacks), pull up to 225', cement to surface, pull tubing out, top off cement, cut wellhead off below plow depth and restore location.

Plugging Proposal Received By: ALAN DUNNING

WitnessType: NONE

Date/Time Plugging Completed: 06/29/2017 3:00 PM

KCC Agent: ALAN DUNNING

Actual Plugging Report:

A one inch cement string was washed to 780 feet and the hole gelled. A 50 ft cement plug was then placed at TD. The cement string was pulled to 500 feet and a 2nd cement plug spotted. The cement string was pulled to 225 ft and the well filled to surface with cement. A total of 28 sacks of portland cement were used to plug well.

Perfs:

Top	Bot	Thru	Comments
649	657		
628	657		

RECEIVED
KCC DIST #3
JUL 10 2017
CHANUTE, KS

AD

INVOICED
AUG 23 2017

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning
(TECHNICIAN)