

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-19196-00-01
Spot: NWNWNW Sec/Twnshp/Rge: 27-25S-5E
4969 feet from S Section Line, 4947 feet from E Section Line
Lease Name: MILLS Well #: 23
County: BUTLER Total Vertical Depth: 2457 feet

Operator License No.: 33192
Op Name: CROWN ENERGY COMPANY
Address: 1117 N.W. 24TH ST.
OKLAHOMA CITY, OK 73106

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	6.625	1962		
PROD	6.625	2406		0 SX
SURF	12	17		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/14/2017 8:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOHN HILL/HAYS WILSON Company: _____ Phone: (405) 526-0111

Proposed
Plugging
Method:

AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 07/14/2017 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TUBING @ 1619', (OUTSIDE OF CASING). QUALITY WELL SERVICE MIXED & PUMPED 85 SXS 60/40 POZMIX 150# HULLS & DISPLACED IN CASING. TAGGED CEMENT @ 1260'. PERFORATED SQUEEZE HOLES @ 250'-251' (4 HOLES). 7-14-2017, RIH W/TUBING @ 260', QUALITY ESTABLISHED CIRCULATION, MIXED & PUMPED 75 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN TUBING, SWEDGED INTO 6" CASING & PUMPED & MIXED 110 SXS 60/40 POZMIX & 4% GEL TO SURFACE, CEMENT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
1940	1950	CSG	
1646	1658	CSG	
1432	1450	CSG	

INVOICED
AUG 24 2017

Remarks: DENIED TA COMPLIANCE LIST

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

14